



## GENERAL NOTES AND SPECIFICATIONS:

- ALL CONSTRUCTION SHALL COMPLY WITH KERMAN MUNICIPAL CODE.
- GROUT ALL CELLS CONTAINING REINFORCING STEEL
- ALL MASONRY UNITS SHALL COMPLY WITH THE LATEST ADOPTED CALIFORNIA BUILDING CODE.
- ALL MASONRY WALLS SHALL BE INSPECTED BY THE CITY OF KERMAN
- DEPTH OF ALL FOOTINGS ARE INTO NATURAL SOIL OR TESTED AND APPROVED COMPACTED FILL
- ALL MASONRY UNITS SHALL BE MINIMUM,  $f_m=1350$  PSI
- REINFORCING STEEL SHALL BE DEFORMED BARS MINIMUM GRADE 40
- FOOTING CONCRETE SHALL BE MINIMUM 2000 PSI AT 28 DAYS
- MORTAR SHALL BE TYPE-S (MINIMUM 1800 PSI AT 28 DAYS)  
ONE (1) PART CEMENT, TYPE-1  
ONE-HALF (1/2) PART LIME PUTTY OR HYDRATED LIME  
FOUR AND ONE-HALF (4 1/2) PARTS SAND (MAXIMUM)
- GROUT SHALL BE A MINIMUM 2000 PSI AT 28 DAYS  
ONE (1) PART CEMENT  
THREE (3) PARTS SAND  
TWO (2) PARTS PEA GRAVEL
- THIS WALL SHALL NOT BE USED TO RETAIN EARTH
- COLOR SHALL BE APPROVED BY CITY OF KERMAN
- ALL WALLS TALLER THAN 6 FEET REQUIRE ENGINEERED PLANS

SIX INCH MASONRY WALL

REVISIONS  
1-15-98  
12-8-05  
5-07-10

CITY OF KERMAN

STD.  
NO.  
M-2